

## Boost LED Driver

1ch High Current LED Controller  
for Automotive

BD18353EFV-M BD18353MUF-M

## General Description

BD18353EFV-M/MUF-M is a 1ch LED Controller. High side current detection amplifier is built-in. PWM dimming duty can be freely set with built-in PWM generation circuit. PWM dimming realizes by driving an external P-ch MOSFET. Outputs abnormal LED status to the FAULT\_B pin. Two systems of analog dimming are built-in. High precision 3.0 V output power supply for analog dimming and PWM dimming setting is built-in.

## Features


- AEC-Q100 Qualified<sup>(Note 1)</sup>
- Functional Safety Supportive Automotive Products
- Rail-to-Rail Current Sense Amplifier
- PWM Dimming Signal Generator
- Over Voltage Protection (OVP)
- Short Circuit Protection (SCP)
- Analog Dimming (two systems)
- DRL Mode (100 % Duty) Enable
- Outputs Abnormal LED Status (FAULT\_B)
- Spread Spectrum Frequency Modulation ON/OFF (SSFM\_B)

(Note 1) Grade1

## Applications

- Automotive Exterior Lamps  
Rear, Turn, DRL/Position, Fog, High/Low Beam etc.


## Typical Application Circuit



○Product structure : Silicon integrated circuit

○This product has no designed protection against radioactive rays.


## Pin Configuration (HTSSOP-B20)



## Pin Description (HTSSOP-B20)

Pin No.	Pin Name	Function
1	VIN	Power supply input
2	EN	Enable input
3	GND	GND
4	VREF3	Reference voltage for analog dimming and PWM dimming duty setting
5	DCDIM1	Analog dimming input
6	DCDIM2	Analog dimming input
7	COMP	Connect capacitor to set feedback compensation
8	RT	Connect resistor to set switching frequency
9	DSET	PWM dimming duty setting voltage input (connect to resistor divider from VREF3 to GND)
10	FAULT_B	Open drain output for fault state flag
11	SSFM_B	Spread spectrum frequency modulation enable input (SSFM enable @SSFM_B = Low)
12	PDRV	P-ch MOSFET gate drive for PWM dimming and LED protection
13	SNSN	Current sense input (-)
14	SNSP	Current sense input (+)
15	OPUD	Output voltage monitor for over voltage protection and under voltage detection (connect to resistor divider from output voltage to GND)
16	PGND	Power GND
17	CS	Inductor current sense input
18	GL	Output for N-ch MOSFET gate drive
19	VDRV5	Bypass with capacitor to provide 5 V bias supply for gate drive
20	DRL/PWMI	DRL mode (100 % duty) enable input / External PWM dimming signal input
-	EXP-PAD	Heat radiation pad. The EXP-PAD is connected to GND.


## Pin Configuration (VQFN20FV3535)

VQFN20FV3535  
(TOP VIEW)

## Pin Description (VQFN20FV3535)

Pin No.	Pin Name	Function
1	GND	GND
2	VREF3	Reference voltage for analog dimming and PWM dimming duty setting
3	DCDIM1	Analog dimming input
4	DCDIM2	Analog dimming input
5	COMP	Connect capacitor to set feedback compensation
6	RT	Connect resistor to set switching frequency
7	DSET	PWM dimming duty setting voltage input (connect to resistor divider from VREF3 to GND)
8	FAULT_B	Open drain output for fault state flag
9	SSFM_B	Spread spectrum frequency modulation enable input (SSFM enable @SSFM_B = Low)
10	PDRV	P-ch MOSFET gate drive for PWM dimming and protection
11	SNSN	Current sense input (-)
12	SNSP	Current sense input (+)
13	OPUD	Output voltage monitor for over voltage protection and under voltage detection (connect to resistor divider from output voltage to GND)
14	PGND	Power GND
15	CS	Inductor current sense input
16	GL	Output for N-ch MOSFET gate drive
17	VDRV5	Bypass with capacitor to provide 5 V bias supply for gate drive
18	DRL/PWMI	DRL mode (100 % duty) enable input / External PWM dimming signal input
19	VIN	Power supply input
20	EN	Enable input
-	EXP-PAD	Heat radiation pad. The EXP-PAD is connected to GND.

## Block Diagram



## Description of Blocks

### 1 Power Supply for N-ch MOSFET Gate Driver and Internal Circuit (VDRV5)

The VDRV5 voltage 5.0 V (Typ) is generated from the VIN pin voltage. This voltage is used as the internal power supply of the IC and the power supply for driving the DC/DC N-ch MOSFET. It also supplies current to the FAULT\_B pin pull up resistor.

The total current supplied to the DC/DC N-ch MOSFET and the resistor must be  $I_{DRV5LM}$  (VDRV5 Output Current Limit) or less.

The current supplied to the DC/DC N-ch MOSFET ( $I_{MOSFET}$ ) can be calculated by the following formula.

$$I_{MOSFET} = Q_G \times f_{SW}$$

Where:

$Q_G$  is the gate charge of the MOSFET.

$f_{SW}$  is the switching frequency.

Connect  $C_{VDRV5} = 2.2 \mu F$  as feedback compensation capacitor to the VDRV5 pin. Place ceramic capacitor close to the IC to minimize trace length to the VDRV5 pin and also to the IC ground.

Do not use the VDRV5 as a power supply other than this IC.

### 2 High Accuracy Reference Voltage (VREF3)

The VREF3 voltage 3.0 V (Typ) is generated from the VDRV5 pin voltage. VREF3 is used as a reference voltage for PWM dimming duty and analog dimming setting. Input the voltage set by resistor dividing from the VREF3 pin to the DSET pin, the DCDIM1 pin, and the DCDIM2 pin.

Do not connect a capacitor to the VREF3 pin.

Do not use the VREF3 as a power supply other than this IC.

### 3 LED Current Setting (CURRENT SENSE)

LED current ( $I_{LED}$ ) can be set by resistor  $R_{SNS}$  connected between the SNSP pin and the SNSN pin.


$$I_{LED} = \frac{V_{SNS\_100\%}}{R_{SNS}} \quad [A]$$

When:

$V_{DCDIM1}, V_{DCDIM2} > V_{DCD\_100\%}$

Where:

$V_{SNS\_100\%}$  is the Current sense threshold voltage.



## Description of Blocks - continued

## 4 PWM Dimming (PWMDIM)

## 4.1 External P-ch MOSFET Drive

The PDRV pin drives an external P-ch MOSFET to achieve PWM dimming. Connect the gate of the P-ch MOSFET to the PDRV pin. The PDRV pin outputs SNSP and SNSP - 7.5 V (Typ).

At start up and restart (After UVLO, TSD, SCP, OVP is released or after EN = High input.), after DC/DC starts switching, the PDRV pin can output SNSP - 7.5 V (Typ).

The PDRV output voltage and the DC/DC output voltage (SNSP voltage) have the characteristics shown below figure. When the number of LED lights is small, design and evaluate in consideration of the characteristics shown below figure. There is a possibility that the external P-ch MOSFET cannot be driven.




Figure 1. PDRV Output Low Voltage vs SNSP Voltage

## 4.2 PWM Dimming Duty Setting

The BD18353EFV-M/MUF-M has a built-in PWM dimming pulse generation circuit. The PWM dimming duty is set by the internal ramp waveform and the voltage input to the DSET pin. The DSET pin voltage is set from VREF3 by a resistor voltage divider.

Setting duty  $D_{PWM}$  can be calculated by the following formula.

$$D_{PWM} = \frac{V_{DSET} - V_{RAMPB}}{V_{RAMPP} - V_{RAMPB}} \times 100 \quad [\%]$$

Where:

$R_{DSET1}$ ,  $R_{DSET2}$  are the PWM dimming duty setting resistor.

$$D_{PWM} = \frac{V_{REF3} \times \frac{R_{DSET2}}{R_{DSET1} + R_{DSET2}} - V_{RAMPB}}{V_{RAMPP} - V_{RAMPB}} \times 100 \quad [\%]$$

If:


$R_{DSET1} = 20 \text{ k}\Omega$ ,  $R_{DSET2} = 10 \text{ k}\Omega$

$$D_{PWM} (\text{Typ}) = \frac{3.00 \times \frac{10 \text{ k}\Omega}{20 \text{ k}\Omega + 10 \text{ k}\Omega} - 0.40}{2.40 - 0.40} \times 100 = 30.0 \quad [\%]$$

Where:

$V_{RAMPP}$  is the internal ramp peak voltage = 2.40 V (Typ).

$V_{RAMPB}$  is the internal ramp bottom voltage = 0.40 V (Typ).




At UVLO detection, OVP detection, SCP detection (during hiccup operation), TSD detection or EN = Low input, the internal ramp waveform becomes  $V_{RAMPB}$  voltage.

#### 4 PWM Dimming (PWMDIM) - continued

##### 4.3 PWM Dimming by External Pulse Signal Input

When the DRL/PWMI pin voltage is  $V_{DRLIH}$  or more, it operates at PWM 100 % duty setting. When the DRL/PWMI pin voltage is  $V_{DRLIL}$  or less, it operates at the PWM dimming duty set by the DSET pin. Therefore, to control PWM dimming with external PWM pulse signal, connect the DSET pin to GND and input the PWM signal to the DRL/PWMI pin.




##### 4.4 DRL Mode (100 % Duty) Enable Input

Switching between PWM dimming mode and DRL mode (100 % Duty) can be done with the input voltage at DRL/PWMI pin. When the DRL/PWMI pin voltage is  $V_{DRLIH}$  or more, it operates at PWM 100 % duty setting. When the DRL/PWMI pin voltage is  $V_{DRLIL}$  or less, it operates at the PWM dimming duty set by the DSET pin.

Because the DRL/PWMI pin is composed of a high-voltage element, it is possible to directly input the battery voltage. The DRL/PWMI pin is pulled down by current.

Considering the short circuit between the DRL/PWMI pin and the VDRV5 pin, it is recommended to insert a limiting resistor  $R_{DRL}$  (47 kΩ or more) as shown below figure.



DRL Mode (100 % Duty) Switching Application Example

## Description of Blocks - continued


## 5 Analog Dimming (DCDIM)

BD18353EFV-M/MUF-M has two systems of analog dimming function. For example, it can be used as in Figure 2. (a) Thermal Derating Function and BIN Setting Function or in Figure 2. (b) Thermal Derating Function and Input Low Voltage Derating Function.

When the DCDIM1 or DCDIM2 pin (The lower voltage takes precedence) becomes 2.2 V (Typ) or less, the LED current decreases.

When not using the analog dimming function, set it to 2.5 V or more, such as connecting DCDIM1, DCDIM2 voltage to the VREF3 pin.


When the analog dimming rate is low, DC/DC control may become unstable and the LED may flicker. Confirm enough in the evaluation.



(a) Thermal Derating Function and BIN Setting Function

(b) Thermal Derating Function and Input Low Voltage Derating Function

Figure 2. Analog Dimming Application Example

Figure 3.  $V_{SNS}$  vs DCDIM1, DCDIM2 Voltage

## Description of Blocks - continued

### 6 Enable Setting (EN)

The BD18353EFV-M/MUF-M can be ON/OFF controlled by the EN pin. It is possible to set the EN pin voltage by a resistor voltage divider from VIN.


$$V_{INON} = \frac{(R_{EN1} + R_{EN2})}{R_{EN2}} \times V_{ENIH} \quad [\text{V}]$$

$$V_{INOFF} = \frac{(R_{EN1} + R_{EN2})}{R_{EN2}} \times V_{ENIL} \quad [\text{V}]$$

Where:

$V_{ENIH}$  is the EN High level threshold voltage = 1.0 V (Typ).

$V_{ENIL}$  is the EN Low level threshold voltage = 0.9 V (Typ).



When the EN pin voltage becomes  $V_{ENIL}$  or less, the PDRV pin outputs High level to turn off external P-ch MOSFET. DC/DC is stopped and the GL pin outputs Low level.

When pulling up to the VIN pin to fix the EN pin to High, considering the short circuit between the EN pin and the GND pin, it is recommended to insert a limiting resistor.

### 7 Switching Frequency Setting (OSC)

The switching frequency of the DC/DC can be set by the resistor  $R_{RT}$  connected to the RT pin.

$$f_{SW1} \doteq \frac{9900}{R_{RT}} \times 10^3 \quad [\text{kHz}] \text{ (200 kHz to 700 kHz)}$$

$$f_{SW2} \doteq \frac{9000}{R_{RT}} \times 10^3 \quad [\text{kHz}] \text{ (2.0 MHz to 2.5 MHz)}$$

### 8 Spread Spectrum Frequency Modulation (SSFM)

BD18353EFV-M/MUF-M has built-in spread spectrum function. It operates at a frequency of  $\pm 6\%$  (Typ) around the frequency  $f_{sw}$  set by  $R_{RT}$ . The spread spectrum function can be set to ON/OFF by the SSFM\_B pin.

To use the spread spectrum function, pull down the SSFM\_B pin to GND.

In case the spread spectrum function will not be used, pull up the SSFM\_B pin to the VDRV5 pin.

Considering a short circuit between the SSFM\_B pin and the PDRV pin, it is recommended to insert a pull up resistor or a pull down resistor (47 kΩ or more).

## Description of Blocks - continued

## 9 Protection Function

## 9.1 Under Voltage Lock Out (UVLO)

UVLO is a protection circuit that prevents IC malfunction at power-on or power-off.

When the VIN pin voltage becomes  $V_{INUVD}$  or less or the VDRV5 pin voltage becomes  $V_{DRV5UVD}$  or less, the PDRV pin outputs high level to turn off external P-ch MOSFET. DC/DC is stopped and GL outputs low level.

## 9.2 Thermal Shutdown (TSD)

TSD shuts down circuits at 175 °C (Typ) and release them at 150 °C (Typ).

## 9.3 Over Current Protection (OCP)

When the CS pin voltage becomes  $V_{CSOCP}$  or more, over current is detected and the GL pin outputs Low until the next switching cycle.

## 9.4 Over Voltage Protection (OVP)

OVP voltage can be set by dividing resistors  $R_{OPUD1}$ ,  $R_{OPUD2}$  connected between DC/DC output and GND.

LED open failure can also be detected by the OVP function.

The detection voltage  $V_{OUT\_OVP}$  is set by the following formula.

$$V_{OUT\_OVP} = \frac{R_{OPUD1} + R_{OPUD2}}{R_{OPUD2}} \times V_{OVP} \quad [V]$$

Where:

$V_{OVP}$  is the over voltage protection detect voltage = 1.00 V (Typ).

When OVP is detected, the PDRV pin outputs high level to turn off the external P-ch MOSFET. DC/DC stops and GL outputs low level. FAULT\_B outputs low level and outputs error detection.

OVP has hysteresis, and when the OPUD pin voltage becomes  $V_{OVP} - V_{OVPHYS}$  or less, DC/DC restarts. When the LED is open, OVP is detected again and the OVP detection operation is repeated.

When OVP is released and the voltage between the SNSP pin and the SNSN pin becomes  $V_{SG}$  (Status Good Voltage) or more, FAULT\_B outputs high level. FAULT\_B holds low output until  $t_{FAULT\_BL}$  elapses after OVP is released.




Figure 4. OVP Setting Circuit




Figure 5. Timing Chart (OVP)

## 9 Protection Function - continued

### 9.5 Internal Over Voltage Protection (INTOVP)


If the LED opens with the resistor  $R_{OPUD1}$  open or the OPUD pin grounded (dual fail), the DC/DC is over voltage and the IC destroyed.

The BD18353EFV-M/MUF-M has an internal OVP circuit that monitors the SNSP pin voltage and prevents destruction of the IC.

However, since the threshold value is fixed ( $V_{INTOVP}$ ), when the absolute voltage of the external parts is low, the parts may be destroyed.

When INTOVP is detected, the PDRV pin outputs High level to turn off the external P-ch MOSFET. DC/DC stops and GL outputs low level. FAULT\_B outputs Low level and outputs error detection. When INTOVP is released and the voltage between the SNSP pin and the SNSN pin becomes  $V_{SG}$  or more, FAULT\_B outputs high level.

FAULT\_B holds low output until  $t_{FAULT\_BL}$  elapses after OVP is released.



INTOVP Circuit

## 9 Protection Function - continued

### 9.6 Under Voltage Detection (UVD)

UVD voltage can be set by dividing resistors  $R_{OPUD1}$ ,  $R_{OPUD2}$  connected between DC/DC output and GND. The detection voltage ( $V_{OUT\_UVD}$ ) is set by the following formula.

$$V_{OUT\_UVD} = \frac{R_{OPUD1} + R_{OPUD2}}{R_{OPUD2}} \times V_{UVD} \quad [\text{V}]$$


Where:

$V_{UVD}$  is the under voltage detection threshold voltage = 100 mV (Typ).

UVD is detected when the OPUD pin voltage become  $V_{UVD}$  or less. UVD is monitored when the voltage between the SNSP pin and the SNSN pin becomes  $V_{SG}$  or more in the ON section of PWM dimming.

After detection the internal counter starts. When the voltage between the SNSP pin and the SNSN pin becomes  $V_{SG}$  or more in the ON section of PWM dimming, it counts up. When the total time reaches  $t_{UVD}$ , the FAULT\_B outputs becomes Low.

After UVLO, TSD, SCP, OVP is released or after EN = High input, until  $t_{UVDDIS}$  has elapsed, UVD does not be detected.



Timing Chart (UVD)

## 9 Protection Function - continued

### 9.7 Short Circuit Protection (SCP)

When the anode of the LED is shorted to GND, the voltage between the SNSP pin and the SNSN pin can be monitored and protected by SCP.

When the voltage between the SNSP pin and the SNSN pin become  $V_{SCPON}$  or more, SCP is detected after SCP delay time ( $t_{SCPDLY}$ ).

When SCP is detected, the PDRV pin outputs High level to turn off the external P-ch MOSFET. DC/DC stops and GL outputs Low level. FAULT\_B outputs Low level and outputs error detection.

Restart after hiccup time ( $t_{HICCUP}$ ) elapses. If the anode of the LED is shorted to GND, the SCP is detected again and the operation is repeated.

FAULT\_B holds Low output until  $t_{FAULT\_BL}$  after restart.




Figure 6. Timing Chart (SCP)

When the anode of the LED is shorted to GND, the voltage between the SNSP pin and the SNSN pin may exceed the absolute voltage. It is recommended to insert a PNP transistor as shown below figure and clamp the voltage. Design to take full consideration of power dissipation of  $R_{SNS}$  and P-ch MOSFET.




Figure 7. Example of Current Clamp Circuit

## Description of Blocks - continued

## 10 Outputs Abnormal Status (FAULT\_B)

The following table summarizes the device behavior under fault condition.

Protection Function	Fault Description Operations			FAULT_B Output
	DC/DC	PDRV Pin	COMP Pin	
EN = Low Detect	OFF	High (= SNSP)	Discharge	Hiz
VIN UVLO Detect	OFF	High (= SNSP)	Discharge	Hiz
VDRV5 UVLO Detect	OFF	High (= SNSP)	Discharge	Hiz
TSD Detect	OFF	High (= SNSP)	Discharge	Hiz
DC/DC OCP Detect	OFF	-	-	-
DC/DC OVP Detect	OFF	High (= SNSP)	Discharge	Low
DC/DC INTOVP Detect	OFF	High (= SNSP)	Discharge	Low
DC/DC UVD Detect	-	-	-	Low (after counting tuVD)
SCP Detect	OFF	High (= SNSP)	Discharge	Low

**Absolute Maximum Ratings (T<sub>j</sub> = 25 °C)**

Parameter	Symbol	Rating	Unit
Supply Pin Voltage (V <sub>IN</sub> )	V <sub>IN</sub>	-0.3 to +70	V
EN, DRL/PWMI Pin Voltage	V <sub>EN</sub> , V <sub>DRL/PWMI</sub>	-0.3 to +70	V
SNSP, SNSN Pin Voltage	V <sub>SNSP</sub> , V <sub>SNSN</sub>	-0.3 to +70	V
PDRV Pin Voltage	V <sub>PDRV</sub>	-0.3 to +70	V
OPUD, SSFM_B Pin Voltage	V <sub>OPUD</sub> , V <sub>SSFM_B</sub>	-0.3 to +70	V
SNSP to OPUD Pin Voltage	V <sub>SNSP_OPUD</sub>	-7 to +70	V
SNSP to SSFM_B Pin Voltage	V <sub>SNSP_SSFMB</sub>	-7 to +70	V
SNSP to SNSN Pin Voltage	V <sub>SNSP_SNSN</sub>	-0.3 to +0.6	V
SNSP to PDRV Pin Voltage	V <sub>SNSP_PDRV</sub>	-0.3 to +10	V
VDRV5 Pin Voltage	V <sub>DRV5</sub>	-0.3 to +7	V
V <sub>IN</sub> to VDRV5 Pin Voltage	V <sub>VIN_DRV5</sub>	-0.3 to +70	V
VREF3, DCDIM1, DCDIM2, COMP, RT, DSET Pin Voltage	V <sub>REF3</sub> , V <sub>DCDIM1</sub> , V <sub>DCDIM2</sub> , V <sub>COMP</sub> , V <sub>RT</sub> , V <sub>DSET</sub>	-0.3 to +7	V
GL, CS Pin Voltage	V <sub>GL</sub> , V <sub>CS</sub>	-0.3 to +7	V
FAULT_B Pin Voltage	V <sub>FAULT_B</sub>	-0.3 to +7	V
Maximum Junction Temperature	T <sub>jmax</sub>	150	°C
Storage Temperature Range	T <sub>stg</sub>	-55 to +150	°C

**Caution 1:** Operating the IC over the absolute maximum ratings may damage the IC. The damage can either be a short circuit between pins or an open circuit between pins and the internal circuitry. Therefore, it is important to consider circuit protection measures, such as adding a fuse, in case the IC is operated over the absolute maximum ratings.

**Caution 2:** Should by any chance the maximum junction temperature rating be exceeded the rise in temperature of the chip may result in deterioration of the properties of the chip. In case of exceeding this absolute maximum rating, design a PCB with thermal resistance taken into consideration by increasing board size and copper area so as not to exceed the maximum junction temperature rating.

Thermal Resistance<sup>(Note 1)</sup>

Parameter	Symbol	Thermal Resistance (Typ)		Unit
		1s <sup>(Note 3)</sup>	2s2p <sup>(Note 4)</sup>	
HTSSOP-B20				
Junction to Ambient	$\theta_{JA}$	143.0	26.8	°C/W
Junction to Top Characterization Parameter <sup>(Note 2)</sup>	$\Psi_{JT}$	8	4	°C/W
VQFN20FV3535				
Junction to Ambient	$\theta_{JA}$	181.9	50.5	°C/W
Junction to Top Characterization Parameter <sup>(Note 2)</sup>	$\Psi_{JT}$	19	7	°C/W

<sup>(Note 1)</sup> Based on JESD51-2A(Still-Air).<sup>(Note 2)</sup> The thermal characterization parameter to report the difference between junction temperature and the temperature at the top center of the outside surface of the component package.<sup>(Note 3)</sup> Using a PCB board based on JESD51-3.<sup>(Note 4)</sup> Using a PCB board based on JESD51-5, 7.

Layer Number of Measurement Board	Material	Board Size
Single	FR-4	114.3 mm x 76.2 mm x 1.57 mm

Top	
Copper Pattern	Thickness
Footprints and Traces	70 $\mu$ m

Layer Number of Measurement Board	Material	Board Size	Thermal Via <sup>(Note 5)</sup>		
			Pitch	Diameter	
4 Layers	FR-4	114.3 mm x 76.2 mm x 1.6 mm	1.20 mm	$\Phi$ 0.30 mm	
Top		2 Internal Layers		Bottom	
Copper Pattern	Thickness	Copper Pattern	Thickness	Copper Pattern	Thickness
Footprints and Traces	70 $\mu$ m	74.2 mm x 74.2 mm	35 $\mu$ m	74.2 mm x 74.2 mm	70 $\mu$ m

<sup>(Note 5)</sup> This thermal via connects with the copper pattern of all layers.

## Recommended Operating Condition

Parameter	Symbol	Min	Typ	Max	Unit
Supply Voltage (VIN) <sup>(Note 1)</sup>	V <sub>IN</sub>	5	13	65	V
Output Voltage (SNSP)	V <sub>SNSP</sub>	-	-	65	V
PWM Frequency Input	f <sub>PWMI</sub>	30	-	2000	Hz
PWM Minimum Pulse Width	t <sub>MIN</sub>	10	-	-	μs
Switching Frequency	f <sub>sw</sub>	200	-	2500	kHz
Operating Ambient Temperature	T <sub>opr</sub>	-40	-	+125	°C

(Note 1) ASO should not be exceeded.

## Recommended Setting Parts Range

Parameter	Symbol	Min	Typ	Max	Unit
Capacitor Connecting to the VIN Pin <sup>(Note 2)</sup>	C <sub>VIN</sub>	1.4	2.2	3.3	μF
Capacitor Connecting to the VDRV5 Pin <sup>(Note 2)</sup>	C <sub>VDRV5</sub>	1.4	2.2	3.3	μF
Capacitor Connecting to the COMP Pin <sup>(Note 2)</sup>	C <sub>COMP</sub>	0.6	1.0	1.5	μF
Total DC/DC Output Capacitor <sup>(Note 2)</sup>	C <sub>OUT</sub>	10	-	-	μF
Resistor Connecting to the EN Pin	R <sub>EN1</sub> , R <sub>EN2</sub>	4.7	-	100	kΩ
Resistor Connecting to the COMP Pin	R <sub>COMP</sub>	-	33	100	Ω
Resistor Connecting to the RT Pin	R <sub>RT</sub>	3.9	-	49	kΩ
Resistor Connecting to the DSET1,DSET2 Pin	R <sub>DSET1</sub> , R <sub>DSET2</sub>	4.7	-	100	kΩ
Resistor Connecting to the FAULT_B Pin	R <sub>FAULT_B</sub>	10	-	-	kΩ
Resistor Connecting to the SSFM_B Pin	R <sub>SSFM_B</sub>	47	-	-	kΩ
Resistor Connecting to the DRL/PWMI Pin	R <sub>DRL</sub>	47	-	-	kΩ

(Note 2) Set the capacitor in consideration of temperature characteristics and DC bias characteristics.

**Electrical Characteristics**(Unless otherwise specified  $V_{IN} = 13\text{ V}$ ,  $T_j = -40\text{ }^\circ\text{C}$  to  $+150\text{ }^\circ\text{C}$ )

Parameter	Symbol	Limit			Unit	Conditions
		Min	Typ	Max		
<b>[Total]</b>						
VIN Circuit Current 1	$I_{IN1}$	-	380	580	$\mu\text{A}$	$V_{EN} = 0\text{ V}$ , No switching
VIN Circuit Current 2	$I_{IN2}$	-	1.7	2.3	$\text{mA}$	$V_{EN} = 5\text{ V}$ $V_{SNSP\_SNSN} > V_{SNS\_100\%}$ $V_{DCDIM1} = V_{DCDIM2} = 3.0\text{ V}$
VIN UVLO Detect Voltage	$V_{INUVD}$	4.10	4.30	4.49	$\text{V}$	VIN falling
VIN UVLO Release Voltage	$V_{INUVR}$	4.49	4.70	4.91	$\text{V}$	VIN rising
VIN UVLO Hysteresis Voltage	$V_{INUVHYS}$	-	0.4	-	$\text{V}$	$V_{INUVR} - V_{INUVD}$
VDRV5 UVLO Detect Voltage	$V_{DRV5UVD}$	3.94	4.15	4.38	$\text{V}$	$V_{DRV5}$ falling
VDRV5 UVLO Release Voltage	$V_{DRV5UVR}$	4.22	4.45	4.68	$\text{V}$	$V_{DRV5}$ rising
VDRV5 UVLO Hysteresis Voltage	$V_{DRV5UVHYS}$	-	0.3	-	$\text{V}$	$V_{DRV5UVR} - V_{DRV5UVD}$
<b>[Reference Voltage]</b>						
VDRV5 Reference Voltage	$V_{DRV5}$	4.76	5.00	5.25	$\text{V}$	$C_{VDRV5} = 2.2\text{ }\mu\text{F}$ $I_{VDRV5} = 0\text{ mA}$ to $10\text{ mA}$ load
VDRV5 Drop Voltage	$V_{DRV5DP}$	-	0.25	0.65	$\text{V}$	$VIN = 4.75\text{ V}$ $I_{VDRV5} = 10\text{ mA}$ load
VDRV5 Output Current Limit	$I_{DRV5LM}$	45	-	-	$\text{mA}$	
VREF3 Reference Voltage	$V_{REF3}$	2.91	3.00	3.09	$\text{V}$	$I_{VREF3} = 0\text{ mA}$ to $2\text{ mA}$ load
VREF3 Output Current Limit	$I_{REF3LM}$	2	-	-	$\text{mA}$	
<b>[EN]</b>						
EN Pull Down Current	$I_{EN}$	0.6	1.2	1.8	$\mu\text{A}$	$V_{EN} = 5\text{ V}$
EN High Level Threshold Voltage	$V_{ENIH}$	0.96	1.00	1.04	$\text{V}$	$V_{EN}$ rising
EN Low Level Threshold Voltage	$V_{ENIL}$	0.86	0.90	0.94	$\text{V}$	$V_{EN}$ falling
EN Hysteresis Voltage	$V_{ENHYS}$	-	0.1	-	$\text{V}$	$V_{ENIH} - V_{ENIL}$
<b>[OSCILLATOR Circuit]</b>						
Switching Frequency 1	$f_{sw1}$	270	300	330	$\text{kHz}$	$R_{RT} = 33\text{ k}\Omega$
Switching Frequency 2	$f_{sw2}$	2070	2300	2530	$\text{kHz}$	$R_{RT} = 3.9\text{ k}\Omega$
RT Output Voltage	$V_{RT}$	-	0.8	-	$\text{V}$	$V_{SSFM\_B} = 4\text{ V}$
Spread Spectrum Frequency	$f_{SSFM}$	-	$f_{sw}/1024$	-	$\text{Hz}$	$V_{SSFM\_B} = 0\text{ V}$
Spread Spectrum Frequency Modulation Width	$f_{SSFMW}$	-	$\pm 6$	-	$\%$	$V_{SSFM\_B} = 0\text{ V}$
SSFM_B High Level Input Voltage	$V_{SSFM\_BIH}$	3.0	-	-	$\text{V}$	Spread spectrum disable
SSFM_B Low Level Input Voltage	$V_{SSFM\_BIL}$	-	-	0.4	$\text{V}$	Spread spectrum enable
SSFM_B Pull Down Resistor	$R_{SSFM\_BD}$	200	400	800	$\text{k}\Omega$	$SSFM\_B = 4\text{ V}$

**Electrical Characteristics - continued**(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = -40$  °C to  $+150$  °C)

Parameter	Symbol	Limit			Unit	Conditions
		Min	Typ	Max		
<b>[N-ch Gate Driver]</b>						
GL ON Resistor High	$R_{GLH}$	-	1.0	2.5	Ω	$I_{GL} = 10$ mA load
GL ON Resistor Low	$R_{GLL}$	-	0.6	1.5	Ω	$I_{GL} = 10$ mA input
Minimum OFF Time 1	$t_{OFFMIN1}$	-	60	-	ns	$R_{RT} = 33$ kΩ
Minimum OFF Time 2	$t_{OFFMIN2}$	-	35	-	ns	$R_{RT} = 3.9$ kΩ
<b>[DC/DC Current Detection]</b>						
Over Current Detection Voltage	$V_{CSOCP}$	275	300	321	mV	$V_{CS}$ rising
CS Pin Leading Edge Blanking Time	$t_{CSBLK}$	-	120	-	ns	
Slope Compensation Current Peak	$I_{CSLPP}$	-	50	-	μA	
CS to COMP Level Shift Voltage	$V_{CSCMPLS}$	-	1.26	-	V	No slope compensation added
<b>[Error Amplifier]</b>						
Trans Conductance	$g_M$	-	1300	-	μS	$V_{SNSP\_SNSN} = 166.5$ mV
COMP Sink Current	$I_{COMPSI}$	-	200	-	μA	$V_{SNSP\_SNSN} = 83.3$ mV $V_{DCDIM1} = V_{DCDIM2} = 0$ V
COMP Source Current	$I_{COMPSO}$	-	200	-	μA	$V_{SNSP\_SNSN} = 83.3$ mV $V_{DCDIM1} = V_{DCDIM2} = 3.0$ V

**Electrical Characteristics - continued**(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = -40$  °C to  $+150$  °C)

Parameter	Symbol	Limit			Unit	Conditions
		Min	Typ	Max		
<b>[Current Sense Amplifier]</b>						
LED Current Sense Voltage 100 %	$V_{SNS\_100\%}$	165.0	166.7	171.7	mV	$T_j = +25$ °C $V_{SNS\_100\%} = V_{SNSP} - V_{SNSN}$ $V_{SNSN} = 0$ V, 30 V $V_{DCDIM1} = V_{DCDIM2} = 2.5$ V
		161.7	166.7	171.7	mV	$T_j = -40$ °C to $+125$ °C $V_{SNS\_100\%} = V_{SNSP} - V_{SNSN}$ $V_{SNSN} = 0$ V, 30 V $V_{DCDIM1} = V_{DCDIM2} = 2.5$ V
LED Current Sense Voltage 90 %	$V_{SNS\_90\%}$	146	150	153	mV	$V_{SNS\_90\%} = V_{SNSP} - V_{SNSN}$ $V_{SNSN} = 0$ V, 30 V $V_{DCDIM1} = 2.0$ V $V_{DCDIM2} = 2.5$ V
LED Current Sense Voltage 10 %	$V_{SNS\_10\%}$	13.7	16.7	19.7	mV	$V_{SNS\_10\%} = V_{SNSP} - V_{SNSN}$ $V_{SNSN} = 0$ V, 30 V $V_{DCDIM1} = 0.4$ V $V_{DCDIM2} = 2.5$ V
Common-mode Input Range High Side Voltage Detection	$V_{SNSN\_HSS}$	1.9	2.0	2.1	V	$V_{SNSN}$ rising
Common-mode Input Range Low Side Voltage Detection	$V_{SNSN\_LSS}$	1.8	1.9	2.0	V	$V_{SNSN}$ falling
SNSP Pin Input Current High Side Voltage	$I_{SNSP\_HSS}$	160	330	530	µA	$V_{SNSP\_SNSN} = 166.5$ mV $V_{SNSN} = 60$ V
SNSN Pin Input Current High Side Voltage	$I_{SNSN\_HSS}$	18	35	54	µA	$V_{SNSP\_SNSN} = 166.5$ mV $V_{SNSN} = 60$ V
SNSP Pin Input Current Low Side Voltage	$I_{SNSP\_LSS}$	-8	-4	-2	µA	$V_{SNSP\_SNSN} = 166.5$ mV $V_{SNSN} = 0$ V
SNSN Pin Input Current Low Side Voltage	$I_{SNSN\_LSS}$	-92	-50	-28	µA	$V_{SNSP\_SNSN} = 166.5$ mV $V_{SNSN} = 0$ V
Short Circuit Protection Threshold Voltage	$V_{SCPON}$	325	350	375	mV	$V_{SNSP\_SNSN}$ rising
Short Circuit Protection Delay Time	$t_{SCPDLY}$	40	50	60	µs	
Hiccup Time	$t_{HICCUP}$	33	40	48	ms	Short circuit detect
<b>[Over Voltage Protection / Under Voltage Detection]</b>						
Over Voltage Protection Detect Voltage	$V_{OVP}$	0.96	1.00	1.04	V	$V_{OUPD}$ rising
Over Voltage Protection Hysteresis Voltage	$V_{OVPHYS}$	-	0.1	-	V	
Under Voltage Detection Threshold Voltage	$V_{UVD}$	-	100	-	mV	
Internal Over Voltage Protection Detect Voltage	$V_{INTOVP}$	65	-	-	V	$V_{SNSP}$ monitor

**Electrical Characteristics - continued**(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = -40$  °C to  $+150$  °C)

Parameter	Symbol	Limit			Unit	Conditions
		Min	Typ	Max		
<b>[PWM Dimming]</b>						
PWM Dimming Frequency	$f_{PWM}$	320	400	480	Hz	
Internal Ramp Bottom Voltage	$V_{RAMPB}$	$V_{REF3} / 3 \times 0.4 - 0.02$	$V_{REF3} / 3 \times 0.4$	$V_{REF3} / 3 \times 0.4 + 0.02$	V	
Internal Ramp Peak Voltage	$V_{RAMPP}$	$V_{REF3} / 3 \times 2.4 - 0.02$	$V_{REF3} / 3 \times 2.4$	$V_{REF3} / 3 \times 2.4 + 0.02$	V	
DSET Pin Input Current	$I_{DSET}$	-	0	1	μA	$V_{DSET} = 3.0$ V
PDRV Pull Up ON Resistor	$R_{PDRV\_U}$	-	20	50	Ω	$I_{PDRV} = 10$ mA load $V_{SNSP} = 30$ V $V_{DSET} = 0$ V, $V_{DRL/PWMI} = 0$ V
PDRV Pull Down Current	$I_{PDRV\_D}$	17	38	65	mA	$V_{SNSP\_PDRV} = 0$ V, $V_{SNSP} = 30$ V $V_{DSET} = 5$ V, $V_{DRL/PWMI} = 0$ V
PDRV Output Low Voltage	$V_{PDRVOL}$	6.5	7.5	9.0	V	$V_{SNSP\_PDRV}, V_{SNSP} = 30$ V
<b>[DRL Mode]</b>						
DRL/PWMI Threshold Voltage DRL Mode	$V_{DRLIH}$	1.42	1.50	1.58	V	$V_{DRL/PWMI}$ rising
DRL/PWMI Threshold Voltage PWM Mode	$V_{DRLIL}$	0.95	1.00	1.05	V	$V_{DRL/PWMI}$ falling
DRL/PWMI Hysteresis Voltage	$V_{DRLIHYS}$	-	0.5	-	V	$V_{DRLIH} - V_{DRLIL}$
DRL/PWMI Pull Down Current	$I_{DRL/PWMI}$	0.5	1.0	2.0	μA	$V_{DRL/PWMI} = 5$ V
<b>[Analog Dimming]</b>						
DCDIM1, DCDIM2 0 % Threshold Voltage	$V_{DCD\_0\%}$	0.17	0.20	0.23	V	$V_{DCDIM1}, V_{DCDIM2}$
DCDIM1, DCDIM2 100 % Threshold Voltage	$V_{DCD\_100\%}$	2.14	2.20	2.26	V	$V_{DCDIM1}, V_{DCDIM2}$
DCDIM1, DCDIM2 Pin Input Current	$I_{DCD}$	-	0	1	μA	$V_{DCDIM1} = V_{DCDIM2} = 3.0$ V
<b>[Outputs LED Status]</b>						
FAULT_B Output Low Voltage	$V_{FAULT\_BOL}$	-	0.1	0.4	V	$I_{FAULT\_B} = 5$ mA input
FAULT_B Leak Current	$I_{FAULT\_B}$	-	0	1	μA	$V_{FAULT\_B} = 5.5$ V
Under Voltage Detection Time	$t_{UVD}$	16	20	24	ms	
Under Voltage Detection Disable Time	$t_{UVDDIS}$	16	20	24	ms	EN = Low to High $V_{IN}$ UVLO release $V_{DRV5}$ UVLO release TSD release
FAULT_B Pin Holds Low Output Time	$t_{FAULT\_BL}$	16	20	24	ms	SCP release OVP release
Status Good Voltage	$V_{SG}$	-	20	-	mV	$V_{SNSP\_SNSN}$ rising


**Typical Performance Curves**(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = +25$  °C)

Figure 8. VIN Circuit Current 1 vs Supply Voltage




Figure 9. VIN Circuit Current 2 vs Supply Voltage




Figure 10. VIN UVLO Detect/Release Voltage vs Temperature




Figure 11. VDRV5 Reference Voltage vs Temperature

**Typical Performance Curves - continued**  
(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = +25$  °C)




Figure 12. VREF3 Reference Voltage vs Temperature  
( $I_{VREF3} = 0$  mA to 2 mA load)




Figure 13. Switching Frequency 1 vs Temperature  
( $R_{RT} = 33$  kΩ)




Figure 14. Switching Frequency 2 vs Temperature  
( $R_{RT} = 3.9$  kΩ)




Figure 15. Minimum OFF Time vs Resistor Connecting to the RT Pin

**Typical Performance Curves - continued**  
(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = +25$  °C)




Figure 16. LED Current Sense Voltage 100 %  
vs Temperature  
( $V_{DCDIM1} = V_{DCDIM2} = 2.5$  V)




Figure 17. LED Current Sense Voltage 90 %  
vs Temperature  
( $V_{DCDIM1} = 2.0$  V,  $V_{DCDIM2} = 2.5$  V)




Figure 18. LED Current Sense Voltage 10 %  
vs Temperature  
( $V_{DCDIM1} = 0.4$  V,  $V_{DCDIM2} = 2.5$  V)




Figure 19. Common-mode Input Range High Side  
Voltage Detection vs Temperature

**Typical Performance Curves - continued**  
(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = +25$  °C)




Figure 20. Over Voltage Protection Detect Voltage vs Temperature




Figure 21. Under Voltage Detection Threshold Voltage vs Temperature




Figure 22. PWM Dimming Frequency vs Temperature




Figure 23. PWM Dimming Duty vs DSET Voltage


**Typical Performance Curves - continued**  
(Unless otherwise specified  $V_{IN} = 13$  V,  $T_j = +25$  °C)

Figure 24. PDRV Output Low Voltage vs Temperature




Figure 25. Hiccup Time vs Temperature




Figure 26. PDRV Output Low Voltage vs SNSP Voltage

**Typical Performance Curves - continued**  
[\(Application Examples 1 BOOST \(Position Mode / DRL Mode\)\)](#)




Figure 27. EN Power ON (DRL Mode)




Figure 28. EN Power ON (PWM Mode)




Figure 29. VIN Power ON (DRL Mode)




Figure 30. VIN Power OFF (DRL Mode)

**Typical Performance Curves - continued**  
 (Application Examples 1 BOOST (Position Mode / DRL Mode))




Figure 31. VIN Power ON (PWM Mode)




Figure 32. VIN Power OFF (PWM Mode)




Figure 33. PWM Mode → DRL Mode




Figure 34. DRL Mode → PWM Mode

**Typical Performance Curves - continued**  
[\(Application Examples 1 BOOST \(Position Mode / DRL Mode\)\)](#)




Figure 35. LED Open Operation (Normal → Open)  
DRL Mode




Figure 36. LED Open Operation (Open → Normal)  
DRL Mode




Figure 37. SCP Operation (Normal → Short)  
DRL Mode




Figure 38. SCP Operation (Short → Normal)  
DRL Mode

**Typical Performance Curves - continued**  
[\(Application Examples 1 BOOST \(Position Mode / DRL Mode\)\)](#)




Figure 39. LED Open Operation (Normal → Open)  
 PWM Mode




Figure 40. LED Open Operation (Open → Normal)  
 PWM Mode




Figure 41. SCP Operation (Normal → Short)  
 PWM Mode




Figure 42. SCP Operation (Short → Normal)  
 PWM Mode

**Typical Performance Curves - continued**  
([Application Examples 1 BOOST \(Position Mode / DRL Mode\)](#))




Figure 43. SSFM Operation (DRL Mode)





Figure 44. SSFM Operation (PWM Mode)

## Application Examples

## 1 BOOST (Position Mode / DRL Mode)

BATT = 8 V to 18 V  
 LED = 8 series, Vf = 3.0 V (Typ), 3.5 V (Max)  
 LED Current = 1.04 A  
 VIN Enable Threshold = 6.1 V  
 OVP Setting Voltage = 51.9 V  
 DC/DC Switching Frequency = 300 kHz



## 1 BOOST (Position Mode / DRL Mode) - continued

## 1.1 Recommended Parts List

Parts	Symbol	Parts Name	Value	Unit	Product Maker
Resistor	IC	BD18353EFV-M/MUF-M	-	-	ROHM
	R <sub>EN1</sub>	MCR03	51	kΩ	ROHM
	R <sub>EN2</sub>	MCR03	10	kΩ	ROHM
	R <sub>DSET1</sub>	MCR03	39	kΩ	ROHM
	R <sub>DSET2</sub>	MCR03	10	kΩ	ROHM
	R <sub>COMP</sub>	MCR03	33	Ω	ROHM
	R <sub>RT</sub>	MCR03	33	kΩ	ROHM
	R <sub>FAULT_B</sub>	MCR03	10	kΩ	ROHM
	R <sub>SSFM_B</sub>	MCR03	47	kΩ	ROHM
	R <sub>PDRV</sub>	MCR03	0	Ω	ROHM
	R <sub>SNS</sub>	LTR18	0.16	Ω	ROHM
	R <sub>OPUD1</sub>	MCR03	560	kΩ	ROHM
	R <sub>OPUD2</sub>	MCR03	11	kΩ	ROHM
	R <sub>CS</sub>	LTR18	0.024	Ω	ROHM
Capacitor	R <sub>GL</sub>	MCR03	10	Ω	ROHM
	R <sub>SLP</sub>	MCR03	0	kΩ	ROHM
	R <sub>DRL</sub>	MCR03	10	kΩ	ROHM
	C <sub>FILT</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>IN1</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>IN2</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>IN3</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>VIN</sub>	GCM188L81H104KA	0.1	μF	murata
	C <sub>EN</sub>	GCM155R71H103KA	0.01	μF	murata
	C <sub>COMP</sub>	GCM21BR11E105KA	1	μF	murata
Inductor	C <sub>OPUD</sub>	GCM155R72A102KA	1000	pF	murata
	C <sub>VDRV5</sub>	GCM21BR71E225KA	2.2	μF	murata
	C <sub>OUT1</sub>	GCJ188R72A104KA	0.1	μF	murata
	C <sub>OUT2</sub> , C <sub>OUT3</sub> , C <sub>OUT4</sub> , C <sub>OUT5</sub>	GCM32DC72A475KE	4.7	μF	murata
	L <sub>FILT</sub>	CLF6045NIT-2R2N-D	2.2	μH	TDK
Diode MOSFET	L1	MSS1278-103MLB	10	μH	Coil Craft
	D1	RBQ10BM65AFHTL	-	-	ROHM
MOSFET	M1	IRLR3110ZTRPB	-	-	Infineon
MOSFET	M2	FDC3535	-	-	ON Semiconductor
Transistor	Q1	SST2907AHZG	-	-	ROHM

## Application Examples - continued


## 2 BOOST to VIN (Position Mode / DRL Mode)

## Position Mode

Position = 13 V  
 LED = 4 series,  $V_f = 3.0$  V (Typ)  
 LED Current = 1.04 A  
 PWM Frequency = 400 Hz  
 PWM Dimming Duty = 10.6 %  
 VIN Enable Threshold = 6.1 V  
 OVP Setting Voltage = 51.9 V  
 DC/DC Switching Frequency = 412 kHz

## DRL Mode

DRL = 13 V  
 LED = 4 series,  $V_f = 3.0$  V (Typ)  
 LED Current = 1.04 A  
 PWM Dimming Duty = 100 %  
 VIN Enable Threshold = 6.1 V  
 OVP Setting Voltage = 51.9 V  
 DC/DC Switching Frequency = 412 kHz



## 2 BOOST to VIN (Position Mode / DRL Mode) - continued

## 2.1 Recommended Parts List

Parts	Symbol	Parts Name	Value	Unit	Product Maker
IC	U1	BD18353EFV-M/MUF-M	-	-	ROHM
Resistor	R <sub>EN1</sub>	MCR03	51	kΩ	ROHM
	R <sub>EN2</sub>	MCR03	10	kΩ	ROHM
	R <sub>DSET1</sub>	MCR03	39	kΩ	ROHM
	R <sub>DSET2</sub>	MCR03	10	kΩ	ROHM
	R <sub>COMP</sub>	MCR03	33	Ω	ROHM
	R <sub>RT</sub>	MCR03	24	kΩ	ROHM
	R <sub>FAULT_B</sub>	MCR03	10	kΩ	ROHM
	R <sub>SSFM_B</sub>	MCR03	47	kΩ	ROHM
	R <sub>PDRV</sub>	MCR03	0	Ω	ROHM
	R <sub>SNS</sub>	LTR18	0.16	Ω	ROHM
	R <sub>OPUD1</sub>	MCR03	680	kΩ	ROHM
	R <sub>OPUD2</sub>	MCR03	18	kΩ	ROHM
	R <sub>CS</sub>	LTR18	0.024	Ω	ROHM
	R <sub>GL</sub>	MCR03	10	Ω	ROHM
Capacitor	R <sub>SLP</sub>	MCR03	2.4	kΩ	ROHM
	R <sub>DRL</sub>	MCR03	10	kΩ	ROHM
	C <sub>FILT</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>IN1</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>IN2</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>IN3</sub>	GCM32ER71H475KA	4.7	μF	murata
	C <sub>VIN</sub>	GCM188L81H104KA	0.1	μF	murata
	C <sub>EN</sub>	GCM155R71H103KA	0.01	μF	murata
	C <sub>COMP</sub>	GCM21BR11E105KA	1	μF	murata
	C <sub>OPUD</sub>	GCM155R72A102KA	1000	pF	murata
Inductor	C <sub>VDRV5</sub>	GCM21BR71E225KA	2.2	μF	murata
	C <sub>OUT1</sub>	GCJ188R72A104KA	0.1	μF	murata
Diode	C <sub>OUT2</sub> , C <sub>OUT3</sub> , C <sub>OUT4</sub> , C <sub>OUT5</sub>	GCM32DC72A475KE	4.7	μF	murata
	L1	MSS1278-103MLB	10	μH	Coil Craft
	D1	RBQ10BM65AFHTL	-	-	ROHM
MOSFET	M1	IRLR3110ZTRPBF	-	-	Infineon
	M2	FDC3535	-	-	ON Semiconductor
Transistor	Q1	SST2907AHZG	-	-	ROHM
	Q2	SST2907AHZG	-	-	ROHM

## Application Examples - continued


## 3 SEPIC

## Position Mode

Position = 13 V  
 LED = 4 series,  $V_f = 3.0$  V (Typ)  
 LED Current = 1.04 A  
 PWM Frequency = 400 Hz  
 PWM Dimming Duty = 10.6 %  
 VIN Enable Threshold = 6.1 V  
 OVP Setting Voltage = 51.9 V  
 DC/DC Switching Frequency = 412 kHz

## DRL Mode

DRL = 13 V  
 LED = 4 series,  $V_f = 3.0$  V (Typ)  
 LED Current = 1.04 A  
 PWM Dimming Duty = 100 %  
 VIN Enable Threshold = 6.1 V  
 OVP Setting Voltage = 51.9 V  
 DC/DC Switching Frequency = 412 kHz



## 3 SEPIC - continued

## 3.1 Recommended Parts List

Parts	Symbol	Parts Name	Value	Unit	Product Maker
IC	U1	BD18353EFV-M/MUF-M	-	-	ROHM
Resistor	R <sub>EN1</sub>	MCR03	51	kΩ	ROHM
	R <sub>EN2</sub>	MCR03	10	kΩ	ROHM
	R <sub>DSET1</sub>	MCR03	39	kΩ	ROHM
	R <sub>DSET2</sub>	MCR03	10	kΩ	ROHM
	R <sub>COMP</sub>	MCR03	15	Ω	ROHM
	R <sub>RT</sub>	MCR03	24	kΩ	ROHM
	R <sub>FAULT_B</sub>	MCR03	10	kΩ	ROHM
	R <sub>SSFM_B</sub>	MCR03	47	kΩ	ROHM
	R <sub>PDdrv</sub>	MCR03	0	Ω	ROHM
	R <sub>SNS</sub>	LTR18	0.16	Ω	ROHM
	R <sub>OPUD1</sub>	MCR03	470	kΩ	ROHM
	R <sub>OPUD2</sub>	MCR03	11	kΩ	ROHM
	R <sub>CS</sub>	LTR18	0.024	Ω	ROHM
	R <sub>GL</sub>	MCR03	10	Ω	ROHM
Capacitor	R <sub>SLP</sub>	MCR03	2.4	kΩ	ROHM
	R <sub>DRL</sub>	MCR03	10	kΩ	ROHM
	C <sub>IN1</sub>	GCM32ER71H475KA	4.7	µF	murata
	C <sub>IN2</sub>	GCM32ER71H475KA	4.7	µF	murata
	C <sub>IN3</sub>	-	-	-	-
	C <sub>VIN</sub>	-	-	-	-
	C <sub>EN</sub>	GCM155R71H103KA	0.01	µF	murata
	C <sub>COMP</sub>	GCM21BR11E105KA	1	µF	murata
	C <sub>OPUD</sub>	GCM155R72A102KA	1000	pF	murata
	C <sub>VDRV5</sub>	GCM21BR71E225KA	2.2	µF	murata
Inductor	C <sub>OUT1</sub>	GCJ188R72A104KA	0.1	µF	murata
	C <sub>SW</sub>	GCM32DC72A475KE	4.7 x 2	µF	murata
Diode	C <sub>OUT2</sub> , C <sub>OUT3</sub> , C <sub>OUT4</sub> , C <sub>OUT5</sub>	GCM32DC72A475KE	4.7	µF	murata
	L1	MSD1278T-103MLB	10	µH	Coil Craft
	D1	RBQ10BM65AFHTL	-	-	ROHM
	M1	IRLR3110ZTRPBF	-	-	Infineon
	M2	FDC3535	-	-	ON Semiconductor
Transistor	Q1	SST2907AHZG	-	-	ROHM

**Application Parts Selection Method (Boost Mode Application)**Refer to [Application Examples 1. BOOST \(Position Mode / DRL Mode\)](#).

A constant setting sheet is available. Contact ROHM directly.

Select application parts by the following procedure.

1. Enable Setting.



2. PWM Dimming Duty Setting.



3. Switching Frequency Setting.

4. Derivation of input peak current ( $I_{L\_MAX}$ ).Feedback of  
change value

5. Over Current protection Setting.



6. Inductor Selection.



7. OVP (LED Open) Detection Voltage Setting.



8. Diode and MOSFET Selection.



9. Output Capacitor Selection.



10. Input Capacitor Selection.



11. Feedback Compensation.



12. Actual Operation Confirmation.

## Application Parts Selection Method (Boost Mode Application) - continued

### 1 Enable Setting

The BD18353EFV-M/MUF-M can be ON/OFF controlled by the EN pin.

Design value:  $V_{INON} = 6.1 \text{ V}$ ,  $V_{INOFF} = 5.5 \text{ V}$

$$V_{INON} = \frac{(R_{EN1} + R_{EN2})}{R_{EN2}} \times V_{ENIH} = \frac{(51 \text{ k}\Omega + 10 \text{ k}\Omega)}{10 \text{ k}\Omega} \times 1.0 = 6.1 \text{ [V]}$$

$$V_{INOFF} = \frac{(R_{EN1} + R_{EN2})}{R_{EN2}} \times V_{ENIL} = \frac{(51 \text{ k}\Omega + 10 \text{ k}\Omega)}{10 \text{ k}\Omega} \times 0.9 = 5.49 \text{ [V]}$$

### 2 PWM Dimming Setting (Internal PWM Dimming Signal Generator)

The BD18353EFV-M/MUF-M has a built-in PWM dimming pulse generation circuit. Set the duty with the built-in ramp waveform and the voltage input to the DSET pin. The DSET pin voltage is set from the VREF3 pin by resistance voltage division.

Design value: PWM Dimming Duty ( $D_{PWM}$ ) = 10.6 %

$$D_{PWM} = \frac{V_{REF3} \times \frac{R_{DSET2}}{R_{DSET1} + R_{DSET2}} - V_{RAMPB}}{V_{RAMPP} - V_{RAMPB}} \times 100$$

$$= \frac{3.00 \times \frac{10 \text{ k}\Omega}{39 \text{ k}\Omega + 10 \text{ k}\Omega} - 0.40}{2.40 - 0.40} \times 100 = 10.6 \text{ [%]}$$

### 3 Switching Frequency Setting

The switching frequency of the DC/DC can be set by the resistor  $R_{RT}$  connected to the RT pin.

Design value: Switching Frequency = 300 kHz

$$f_{SW1} \doteq \frac{9900}{R_{RT}} \times 10^3 = \frac{9900}{33 \text{ k}\Omega} \times 10^3 = 300 \text{ [kHz]}$$

## Application Parts Selection Method (Boost Mode Application) - continued

4 Derivation of Input Peak Current  $I_{L\_MAX}$  ( $V_{DCDIM1} > 2.5$  V,  $V_{DCDIM2} > 2.5$  V)4.1 Calculation of Output Voltage ( $V_{OUT}$ )  
BOOST Setting:

$$V_{OUT} = V_{f\_LED} \times N + V_{SNS\_100\%} + R_{ON\_PWMFET} \times I_{LED}$$

$$= 3 \times 8 + 0.1667 + 0.2 \times 1 \approx 24.4 \quad [V]$$

Where:

$V_{f\_LED}$  is the Vf of LED (Typ: 3.0 V, Max: 3.5 V).  
 $N$  is the number of series LED.  
 $R_{ON\_PWMFET}$  is the ON resistance of MOSFET for PWM Dimming. (M1)  
 $I_{LED}$  is the output LED current.

4.2 Calculation of DC/DC Switching Duty ( $D_{SW}$ )

$$D_{SW} = \frac{V_{OUT} - V_{IN}}{V_{OUT}} = \frac{24V - 13V}{24V} \approx 0.458$$

4.3 Calculation of Output Current ( $I_{LED}$ )

$$I_{LED} = \frac{V_{SNS\_100\%}}{R_{SNS}} = \frac{0.1667}{0.16} \approx 1.04 \quad [A]$$

4.4 Calculation of Input Peak Current ( $I_{L\_MAX}$ )

$$I_{L\_MAX} = I_{L\_AVE\_MAX} + \frac{1}{2} \Delta I_{L\_MAX} = 3.90 + 1.30 = 5.2 \quad [A]$$

$$I_{L\_MIN} = I_{L\_AVE\_MIN} - \frac{1}{2} \Delta I_{L\_MAX} = 1.48 - 1.30 = 0.18 \quad [A]$$

$$I_{L\_AVE\_MAX} = \frac{V_{OUT\_MAX} \times I_{LED}}{\eta \times V_{IN\_MIN}} = \frac{28V \times 1A}{0.9 \times 8} \approx 3.90 \quad [A]$$

$$I_{L\_AVE\_MIN} = \frac{V_{OUT\_MIN} \times I_{LED}}{\eta \times V_{IN\_MAX}} = \frac{24V \times 1A}{0.9 \times 18} \approx 1.48 \quad [A]$$

$$\Delta I_{L\_MAX} = \frac{V_{IN}}{L} \times \frac{(V_{OUT} - V_{IN})}{V_{OUT}} \times \frac{1}{f_{SW\_MIN}}$$

$$= \frac{14V}{10 \mu H} \times \frac{(28V - 14V)}{28V} \times \frac{1}{270 \text{ kHz}} \approx 2.59 \quad [A]$$

Where:

$I_{L\_MAX}$  is the maximum inductor current.  
 $I_{L\_MIN}$  is the minimum inductor current.  
 $I_{L\_AVE}$  is the mean inductor current.  
 $I_{L\_AVE\_MAX}$  is the maximum mean inductor current.  
 $I_{L\_AVE\_MIN}$  is the minimum mean inductor current.  
 $\Delta I_{L\_AVE}$  is the maximum inductor ripple current.  
 $\eta$  is the Efficiency.  
 $f_{SW\_MIN}$  is the minimum switching frequency.

- Assign minimum input voltage for calculation.
- BD18353EFV-M/MUF-M adopts current mode DC/DC converter control. When  $I_{L\_MIN}$  is positive, it becomes to be in the consecutive modes, and it will be in the discontinuity mode when  $I_{L\_MIN}$  is negative. Feedback characteristics are easy to become insufficient in the discontinuous mode, and responsiveness turns worse, and a switching waveform pattern becomes irregular, and stability is easy to turn worse. Therefore it is sufficient validation of feedback characteristics are recommended.
- $\eta$  (efficiency) is calculated as 90 %.
- In the case of  $V_{DCDIM1} \leq 2.5$  V or  $V_{DCDIM2} \leq 2.5$  V, calculate  $I_{LED}$  with reference to [Description of Blocks 5 Analog Dimming \(DCDIM\)](#).

## Application Parts Selection Method (Boost Mode Application) - continued

### 5 Over Current Protection Setting

Select  $R_{CS}$  (resistance for over current detection) to realize below.

Design value: Over current detection = 12.5 A

$$I_{OCP\_MIN} = \frac{V_{CSOCP\_MIN}}{R_{CS}} > I_{L\_MAX} \quad [A]$$

$$I_{OCP\_MIN} = \frac{V_{CSOCP\_MIN}}{R_{CS}} = \frac{0.275}{0.024} \approx 11.46 > 5.2 \quad [A]$$

Where:

$I_{OCP\_MIN}$  is the minimum over current detection current.

$V_{CSOCP\_MIN}$  is the minimum over current detection voltage.

Set a sufficient margin in consideration of the variation of the inductor.

### 6 Inductor Selection

For the purpose of stabilizing current mode DC/DC converter operation, adjustment of L value within the following condition is recommended.

Design value:  $R_{SLP} = 0.0 \text{ k}\Omega$

$$L > \frac{(V_{OUT} - V_{IN}) \times R_{CS} \times R_{RT} \times 1.5 \times 10^{-6}}{4k + R_{SLP}}$$

$$L > \frac{(28 - 8) \times 24.24 \text{ m} \times 33.33 \text{ k} \times 1.5 \times 10^{-6}}{4k} \approx 6 \quad [\mu\text{H}]$$

Design value:  $R_{SLP} = 1.2 \text{ k}\Omega$

$$L > \frac{(28 - 8) \times 24.24 \text{ m} \times 33.33 \text{ k} \times 1.5 \times 10^{-6}}{4k + 1.2k} \approx 4.7 \quad [\mu\text{H}]$$

Reduction of calculated value will increase stability, but may reduce responsiveness such as power voltage variation. If the above formula is not satisfied, the switching becomes unstable due to sub-harmonic oscillation, and the LED may flicker. The condition can be eased by adding  $R_{SLP}$ . However, be aware that adding  $R_{SLP}$  will also change OCP detection ( $I_{OCP}$ ) level. The formula for calculating the OCP detection level ( $I_{OCP}$ ) when  $R_{SLP}$  is added is as follows.

Design value:  $R_{SLP} = 1.2 \text{ k}\Omega$

$$I_{OCP\_MIN} = \frac{\left( V_{CSOCP\_MIN} - \frac{1.06}{R_{RT} \times 1.2 \times 10^{-6}} \times \frac{D_{SW\_MAX}}{f_{SW\_MIN}} \times R_{SLP} \right)}{R_{CS}} > I_{L\_MAX} \quad [A]$$

$$I_{OCP\_MIN} = \frac{\left( 0.275 - \frac{1.06}{33k \times 1.2 \times 10^{-6}} \times \frac{0.72}{270k} \times 1.2k \right)}{0.024} \approx 7.89 > I_{L\_MAX} \quad [A]$$

Where:

$D_{SW\_MAX}$  is the maximum DC/DC switching duty.

$f_{SW\_MIN}$  is the minimum switching frequency.

$I_{L\_MAX}$  is the maximum inductor current.

## Application Parts Selection Method (Boost Mode Application) - continued

### 7 OVP (LED Open) Detection Voltage Setting

LED open detection voltage needs higher voltage setting than overshoot of output voltage at start up to avoid start up failure. Further, output voltage at the time of LED open detection ( $V_{OUT\_OVP}$ ) is calculable as shown below by setting  $R_{OPUD1}$  and  $R_{OPUD2}$ .

Design value: Over voltage detection = 51.9 V

$$V_{OUT\_OVP} = \frac{R_{OPUD1} + R_{OPUD2}}{R_{OPUD2}} \times V_{OVP}$$

$$= \frac{560\ k + 11\ k}{11\ k} \times 1.0\ V \approx 51.9\ (Typ) \quad [V]$$

Where:

$V_{OUT\_OVP}$  is the OVP (LED Open) Detection Voltage.

$R_{OPUD1}$ ,  $R_{OPUD2}$  resistor will be the current discharge path for the output capacitor when PWM = Low.

Improperly the resistor value can increase VOUT ripple and cause the LED to flicker. Therefore, it is recommended to select  $R_{OPUD1}$  in the range of 500 kΩ to 1000 kΩ.

Sufficient verification for LED flickering is required with actual application as behavior differs by characteristic of output capacitor and LED. ( $V_{OUT}$  drop can be prevented by inserting bigger output capacitor or ODT resistance.)

## 8 Diode and MOSFET Selection

### Selection of MOSFET M1

Select a MOSFET (M1) whose VDS rating is higher than the maximum voltage for OVP (LED open) detection.

$$M1\ V_{DS} > V_{OUT\_OVP\_MAX} = \frac{R_{OPUD1} + R_{OPUD2}}{R_{OPUD2}} \times V_{OVP\_MAX}$$

$$= \frac{560\ k + 11\ k}{11\ k} \times 1.04\ V \approx 54\ (Max) \quad [V]$$

Where:

$M1\ V_{DS}$  is the maximum rating voltage between drain and source of M1.

$V_{OUT\_OVP\_MAX}$  is the maximum over voltage detection voltage.

The RMS current rating ( $I_{DS\_RMS}$ ) flowing between the drain - source of M1 can be calculated as follows.

$$I_{DS\_RMS} = 1.3 \times \sqrt{(I_{L\_AVE})^2 \times D_{SW}}$$

Where:

$I_{L\_AVE}$  is the mean inductor current.

$D_{SW}$  is the Switching Duty.

A loss of M1 is calculated next. The loss of M1 has Switching loss  $P_{LOSS1}$  and M1 On resistance loss  $P_{LOSS2}$ . Switching loss  $P_{LOSS1}$  and M1 On resistance loss  $P_{LOSS2}$  can be calculated as follows.

$$P_{LOSS1} = \frac{(t_R + t_F)}{2} \times f_{SW} \times (V_{OUT} + V_{D1}) \times I_{L\_AVE}$$

$$P_{LOSS2} = I_{L\_AVE}^2 \times R_{ON} \times D_{SW}$$

Where:

$t_R$  is the rise time of M1 drain-source.

$t_F$  is the fall time of M1 drain-source.

$V_{D1}$  is the forward voltage of D1.

$R_{ON}$  is the ON resistance of M1.

## 8 Diode and MOSFET Selection - continued

### Selection of rectifier diode D1

For power consumption reduction, use a Schottky Barrier diode for rectification diode D1. The withstand voltage rating of the diode shall be higher than the OVP (LED Open) detection voltage. In addition, Schottky Barrier diode with low leakage current shall be selected if PWM dimming is used. Because the leakage current increases with higher temperature environment, the output capacitor can be discharged in PWM = Low which may result that LED current will be unstable. The current limit of D1 can be calculated in following formula.

$$I_{D1} = I_{L\_AVE} \times (1 - D_{SW})$$

Where:

$I_{L\_AVE}$  is the mean inductor current.

$D_{SW}$  is the DC/DC switching duty.

### Selection of MOSFET M2

Consider margin and set the rated voltage rather higher than the actual usage condition for LED current and output voltage.

### Selection of transistor Q1 for current clamp

It is recommended to insert Q1 to control the flow of excessive large current at the time of anode ground fault. By inserting Q1, the set current is clamped by the Vf of Q1, so the withstand current of M2 can be suppressed.

For example, when Vf = 0.5 V, the current is clamped at about 3 times the set current. Select the Vce of Q1 that satisfies the following formula.

$$V_{CE} > V_{OUT\_OVP\_MAX}$$

Also, select in consideration of hfe, speed and saturation voltage.

## 9 Output Capacitor Selection

Output capacity includes two purposes. The first is to reduce output ripple. The second is to supply current to LED when MOSFET (D1) is switched on. The output voltage ripple is influenced by both bulk capacity and ESR. (When a ceramic capacitor is used, most of the ripple caused by bulk capacity.) Bulk capacity and the ESR can be calculated in lower formula.

$$C_{OUT} \geq I_{LED} \times \frac{D_{SW\_MAX}}{\Delta V_{COUT} \times f_{SW\_MIN}}$$

$$R_{ESR} < \frac{\Delta V_{ESR}}{I_{L\_MAX}}$$

Where:

$\Delta V_{COUT}$  is the influence with the capacitor among output ripple.

$\Delta V_{ESR}$  is the ripple which occurs in the ESR of the output capacitor.

$f_{SW\_MIN}$  is the minimum switching frequency.

The total output ripple permitted here can be expressed as product of LED current ripple and the equivalent resistance of the LED. This equivalent resistance is defined as " $\Delta V / \Delta I$  of the LED current", and it is necessary to calculate from I-V properties in the data sheet of the selected LED. When the application condition is the number of the driven LED = 8 pcs (equivalent resistance 0.2  $\Omega$  / LED), LED current = 1 A ( $I_{L\_MAX} = 5.2$  A), switching duty = 72 % ( $V_{IN} = 8$  V,  $V_{OUT} = 28$  V), switching frequency = 300 kHz, LED current ripple = 5%. Then the total output ripple can be calculated as follows.

$$V_{OUT\_RIPPLE} = 1 A \times 5 \% \times (0.2 \Omega \times 8) = 80 \quad [\text{mV}]$$

Where:

$V_{OUT\_RIPPLE}$  is the  $V_{OUT}$  ripple voltage.

If bulk capacity causes 95 % among total output ripple, the output capacitor is calculated as follows.

$$C_{OUT} \geq 1 \times \frac{0.72}{0.08 \times 0.95} \times \frac{1}{300 \text{ kHz}} \approx 31.6 \quad [\mu\text{F}]$$

$$R_{ESR} < \frac{V_{OUT\_RIPPLE}}{I_{L\_MAX}} = \frac{(0.08 \times 0.05)}{5.2} \approx 0.77 \quad [\text{m}\Omega]$$

## 9 Output Capacitor Selection - continued

However the capacitance of output capacitor mentioned above is minimum capacitance. Therefore select parts considering the tolerance of the capacitor and DC bias properties. Furthermore, because small external part connected to output may lead to bigger ripple on output voltage, which may result in LED flickering, sufficient verification of the actual application is required. Increase output capacitors if judged to be required from the verification. In addition, an acoustic noise may be produced by the piezoelectric effect of the ceramic capacitor during PWM dimming. Low ESR electrolytic capacitor used together with a ceramic capacitor may reduce this noise. But capacitance may largely decrease with a change of the voltage with the ceramic capacitor and may not accord with the numerical value calculated from theory.

## 10 Input Capacitor Selection

In DC/DC converter, since peak current flows between input and output, a capacitor is also required in the input side. Therefore, low ESR capacitors with capacitor of 10  $\mu$ F or more and ESR component of 100 m $\Omega$  or less are recommended as input capacitors. If a capacitor out of the range is selected, an excessive ripple voltage may be superimposed on the input voltage and the LSI may malfunction.

$$C_{IN} \geq \frac{\Delta I_L}{8 \times V_{IN\_RIPPLE} \times f_{SW}}$$

Where:

$V_{IN\_RIPPLE}$  is the  $V_{IN}$  ripple voltage.

## 11 Feedback Compensation

- Concerning stability condition of application.  
Stability condition for system with negative feedback is as shown below.  
Phase-lag when gain is 1 (0 dB) is no more than 150 ° (namely, phase margin is 30 ° or more).  
Further, since DC/DC converter application is sampled by switching frequency, GBW of the entire system is set to be 1 / 10 or less of switching frequency. To wrap up, target characteristics of application are as shown below.
- Phase-lag when gain is 1 (0 dB) is 150 ° or less (namely, phase margin is 30 ° or more).
- GBW at the time (namely, frequency when gain is 0 dB) is 1/10 or less of switching frequency. Therefore, in order to raise responsiveness by limiting GBW, higher switching frequency is required.
- Phase margin: 60 ° or more
- GBW: 1/20 or less of switching frequency.  
is recommended.

The knack for securing stability feedback compensation is to insert phase-lead  $f_{Z1}$  near GBW. GBW is determined by  $C_{OUT}$  and phase-lag  $f_P$  due to output impedance  $R_L$  ( $= V_{OUT} / I_{LED}$ ).

They are shown in the following formulae.

### Phase-lead

$$f_{Z1} = \frac{1}{2 \pi \times C_{COMP} \times R_{COMP}}$$

### Phase-lag

$$f_P = \frac{1}{2 \pi \times R_L \times C_{OUT}}$$

$$R_L = \frac{V_{OUT}}{I_{LED}}$$

As described above, secure phase margin. For  $R_L$  value at max load should be inserted. In addition, with boost DC/DC, right half plane zero (RHP zero) is to be considered. This zero has a characteristic of zero as a gain and as the pole with phase. Because it causes an oscillation when this zero effects on a control loop, it is necessary to bring GBW just before RHP zero. RHP zero  $f_{Z2}$  can be calculated with an equation below and shows good characteristic by setting GBW to be lower than 1/10 of RHP zero or less.

$$f_{Z2} = \frac{R_L \times (\frac{V_{IN}}{V_{OUT}})^2}{2 \pi \times L}$$

## 11 Feedback Compensation - continued

Particularly when supply voltage rises and gets close to output voltage, the switching output becomes irregular and ripple of the output voltage increases. Ripple of the LED current may thereby get bigger.

Since this setting is obtained by simplified, not strict, calculation, adjustment by actual equipment may be required in some cases.

Further, since these characteristics will vary depending upon substrate layout, load condition, etc., confirm satisfactorily with actual equipment when planning mass production.

## 12 Actual Operation Confirmation

Select external parts based on verification with actual equipment since characteristics will vary depending on various factors such as load current, input voltage, output voltage, inductor value, load capacity, switching frequency and mounting pattern.

### About the attention point at the time of the PCB layout









1. Locate the decoupling capacitor of  $C_{VIN}$ ,  $C_{VDRV5}$  close to an LSI pin as much as possible.
2.  $R_{RT}$  locates it close to the RT pin, and prevent there from being capacity.
3. Because high current may flow in PGND, lower impedance.
4. Prevent noise to be applied to the EN, VREF3, COMP, RT, DCDIM1, DCDIM2, DSET, OPUD, SNSP and SNSN pins.
5. As the GL, CS, PDRV pins are switching, be careful not to affect the neighboring patterns.
6. There is EXP-PAD on the back side of the package.
7. For noise reduction, PGND of  $R_{CS}$  and PGND of  $C_{OUT}$  recommend to have one common grounds. In addition, consider the PCB layout so that the current path of  $M1 \rightarrow R_{CS}, R_{CS} \rightarrow PGND$  and the current path of  $M1 \rightarrow D1 \rightarrow C_{OUT} \rightarrow PGND$  are the shortest and with the lowest impedance on the same surface without vias etc.

## I/O Equivalence Circuits

Pin No.	Pin Name	I/O Equivalence Circuit	Pin No.	Pin Name	I/O Equivalence Circuit
2 (20)	EN		4 (2)	VREF3	
5 (3)	DCDIM1		7 (5)	COMP	
6 (4)	DCDIM2				
8 (6)	RT		9 (7)	DSET	
10 (8)	FAULT_B		11 (9)	SSFM_B	

( ) is the VQFN20FV3535 package

## I/O Equivalence Circuits- continued

Pin No.	Pin Name	I/O Equivalence Circuit	Pin No.	Pin Name	I/O Equivalence Circuit
12 (10)	PDRV	 <p>SNSP - 7.5 V</p>	13 (11)	SNSN	
			14 (12)	SNSP	
15 (13)	OPUD		17 (15)	CS	
18 (16)	GL		19 (17)	VDRV5	
20 (18)	DRL/ PWMI				

( ) is the VQFN20FV3535 package.

## Operational Notes

### 1. Reverse Connection of Power Supply

Connecting the power supply in reverse polarity can damage the IC. Take precautions against reverse polarity when connecting the power supply, such as mounting an external diode between the power supply and the IC's power supply pins.

### 2. Power Supply Lines

Design the PCB layout pattern to provide low impedance supply lines. Furthermore, connect a capacitor to ground at all power supply pins. Consider the effect of temperature and aging on the capacitance value when using electrolytic capacitors.

### 3. Ground Voltage

Ensure that no pins are at a voltage below that of the ground pin at any time, even during transient condition.

### 4. Ground Wiring Pattern

When using both small-signal and large-current ground traces, the two ground traces should be routed separately but connected to a single ground at the reference point of the application board to avoid fluctuations in the small-signal ground caused by large currents. Also ensure that the ground traces of external components do not cause variations on the ground voltage. The ground lines must be as short and thick as possible to reduce line impedance.

### 5. Recommended Operating Conditions

The function and operation of the IC are guaranteed within the range specified by the recommended operating conditions. The characteristic values are guaranteed only under the conditions of each item specified by the electrical characteristics.

### 6. Inrush Current

When power is first supplied to the IC, it is possible that the internal logic may be unstable and inrush current may flow instantaneously due to the internal powering sequence and delays, especially if the IC has more than one power supply. Therefore, give special consideration to power coupling capacitance, power wiring, width of ground wiring, and routing of connections.

### 7. Testing on Application Boards

When testing the IC on an application board, connecting a capacitor directly to a low-impedance output pin may subject the IC to stress. Always discharge capacitors completely after each process or step. The IC's power supply should always be turned off completely before connecting or removing it from the test setup during the inspection process. To prevent damage from static discharge, ground the IC during assembly and use similar precautions during transport and storage.

### 8. Inter-pin Short and Mounting Errors

Ensure that the direction and position are correct when mounting the IC on the PCB. Incorrect mounting may result in damaging the IC. Avoid nearby pins being shorted to each other especially to ground, power supply and output pin. Inter-pin shorts could be due to many reasons such as metal particles, water droplets (in very humid environment) and unintentional solder bridge deposited in between pins during assembly to name a few.

### 9. Unused Input Pins

Input pins of an IC are often connected to the gate of a MOS transistor. The gate has extremely high impedance and extremely low capacitance. If left unconnected, the electric field from the outside can easily charge it. The small charge acquired in this way is enough to produce a significant effect on the conduction through the transistor and cause unexpected operation of the IC. So unless otherwise specified, unused input pins should be connected to the power supply or ground line.

## Operational Notes – continued


### 10. Regarding the Input Pin of the IC

This monolithic IC contains P+ isolation and P substrate layers between adjacent elements in order to keep them isolated. P-N junctions are formed at the intersection of the P layers with the N layers of other elements, creating a parasitic diode or transistor. For example (refer to figure below):

When GND > Pin A and GND > Pin B, the P-N junction operates as a parasitic diode.

When GND > Pin B, the P-N junction operates as a parasitic transistor.

Parasitic diodes inevitably occur in the structure of the IC. The operation of parasitic diodes can result in mutual interference among circuits, operational faults, or physical damage. Therefore, conditions that cause these diodes to operate, such as applying a voltage lower than the GND voltage to an input pin (and thus to the P substrate) should be avoided.



Example of Monolithic IC Structure

### 11. Ceramic Capacitor

When using a ceramic capacitor, determine a capacitance value considering the change of capacitance with temperature and the decrease in nominal capacitance due to DC bias and others.

### 12. Thermal Shutdown Circuit (TSD)

This IC has a built-in thermal shutdown circuit that prevents heat damage to the IC. Normal operation should always be within the IC's maximum junction temperature rating. If however the rating is exceeded for a continued period, the junction temperature ( $T_j$ ) will rise which will activate the TSD circuit that will turn OFF power output pins. When the  $T_j$  falls below the TSD threshold, the circuits are automatically restored to normal operation.

Note that the TSD circuit operates in a situation that exceeds the absolute maximum ratings and therefore, under no circumstances, should the TSD circuit be used in a set design or for any purpose other than protecting the IC from heat damage.

### 13. Over Current Protection Circuit (OCP)

This IC incorporates an integrated overcurrent protection circuit that is activated when the load is shorted. This protection circuit is effective in preventing damage due to sudden and unexpected incidents. However, the IC should not be used in applications characterized by continuous operation or transitioning of the protection circuit.

### 14. Functional Safety

“ISO 26262 Process Compliant to Support ASIL-<sup>\*</sup>”

A product that has been developed based on an ISO 26262 design process compliant to the ASIL level described in the datasheet.

“Safety Mechanism is Implemented to Support Functional Safety (ASIL-<sup>\*</sup>)”

A product that has implemented safety mechanism to meet ASIL level requirements described in the datasheet.

“Functional Safety Supportive Automotive Products”



A product that has been developed for automotive use and is capable of supporting safety analysis with regard to the functional safety.

Note: “ASIL-<sup>\*</sup>” is stands for the ratings of “ASIL-A”, “-B”, “-C” or “-D” specified by each product's datasheet.

## Ordering Information



## Marking Diagrams



## Physical Dimension and Packing Information

Package Name: HTSSOP-B20

6. 5 ± 0. 1  
(Max 6. 85 (include. BURR)  
(4. 0)

2 0 1 1

6. 4 ± 0. 2  
4. 4 ± 0. 1

0. 325

1 10

0. 5 ± 0. 15  
1. 0 ± 0. 2

0. 17 ± 0. 05  
0. 08 S

1. 0 MAX  
0. 85 ± 0. 05  
0. 08 ± 0. 05

0. 65 0. 24 ± 0. 04

(UNIT : mm)

PKG : HTSSOP-B20

Drawing No. EX192-5002

< Tape and Reel Information >

Tape	Embossed carrier tape
Quantity	2500pcs
Direction of feed	E2 The direction is the pin 1 of product is at the upper left when you hold reel on the left hand and you pull out the tape on the right hand

Reel




Pocket Quadrants

Direction of feed

## Physical Dimension and Packing Information

Package Name

VQFN20FV3535




(UNIT : mm)  
 PKG : VQFN20FV3535  
 Drawing No. EX375-5001-4

NOTE: Dimensions in ( ) for reference only.

&lt; Tape and Reel Information &gt;

Tape	Embossed carrier tape
Quantity	2500pcs
Direction of feed	E2 The direction is the pin 1 of product is at the upper left when you hold reel on the left hand and you pull out the tape on the right hand



## Revision History

Date	Revision	Changes
16.Mar.2020	001	<p>New Release</p> <p>Change <a href="#">Electrical Characteristics</a></p> <p>VDRV5 Reference Voltage Before: <math>I_{VDRV5} = 0</math> mA to 10 mA After: <math>I_{VDRV5} = 0</math> mA to 10 mA load</p> <p>VDRV5 Drop Voltage Before: <math>I_{VDRV5} = 10</math> mA After: <math>I_{VDRV5} = 10</math> mA load</p> <p>VREF3 Reference Voltage Before: <math>I_{VREF3} = 0</math> mA to 2 mA After: <math>I_{VREF3} = 0</math> mA to 2 mA load</p> <p>OSCILLATOR Circuit Before: Spread Spectrum Frequency Modulation Width After: Spread Spectrum Frequency Modulation Width</p> <p>GL ON Resistor High Before: <math>I_{GL} = -10</math> mA After: <math>I_{GL} = 10</math> mA load</p> <p>GL ON Resistor Low Before: <math>I_{GL} = +10</math> mA After: <math>I_{GL} = 10</math> mA input</p> <p>COMP Sink Current Before: <math>V_{DCDIM} = 0</math> V After: <math>V_{DCDIM1} = V_{DCDIM2} = 0</math> V</p>
05.Feb.2021	002	<p>Internal Ramp Bottom Voltage Before: (Min) 0.38 (Typ) 0.40 (Max) 0.42 After: (Min) <math>V_{REF3} / 3 \times 0.4 - 0.02</math> (Typ) <math>V_{REF3} / 3 \times 0.4</math> (Max) <math>V_{REF3} / 3 \times 0.4 + 0.02</math> Deletion: <math>V_{REF3} = 3.0</math> V</p> <p>Internal Ramp Peak Voltage Before: (Min) 2.38 (Typ) 2.40 (Max) 2.42 After: (Min) <math>V_{REF3} / 3 \times 2.4 - 0.02</math> (Typ) <math>V_{REF3} / 3 \times 2.4</math> (Max) <math>V_{REF3} / 3 \times 2.4 + 0.02</math> Deletion: <math>V_{REF3} = 3.0</math> V</p> <p>PDRV Pull Up ON Resistor Before: <math>V_{SNSP\_PDRV} = 7</math> V, <math>V_{SNSP} = 30</math> V, <math>V_{DSET} = 5</math> V, <math>V_{DRL/PWM} = 0</math> V After: <math>I_{PDRV} = 10</math> mA load, <math>V_{SNSP} = 30</math> V, <math>V_{DSET} = 0</math> V, <math>V_{DRL/PWMI} = 0</math> V</p> <p>PDRV Pull Down Current Before: <math>V_{DSET} = 0</math> V, <math>V_{DRL/PWM} = 0</math> V After: <math>V_{DSET} = 5</math> V, <math>V_{DRL/PWMI} = 0</math> V</p> <p>FAULT_B Output Low Voltage Before: <math>I_{FAULT\_B} = 5</math> mA After: <math>I_{FAULT\_B} = 5</math> mA input</p> <p>Change <a href="#">Typical Performance Curves</a> Before: VREF3 Reference Voltage vs Temperature (<math>I_{VREF3} = 0</math> mA to 2 mA) After: VREF3 Reference Voltage vs Temperature (<math>I_{VREF3} = 0</math> mA to 2 mA load)</p> <p>Change Application Examples <a href="#">SEPIC Recommended Parts List</a> Inductor L1 Before: MSS1278T-103MLB After: MSD1278T-103MLB</p> <p>Append <a href="#">14. Functional Safety</a></p>

# Notice

## Precaution on using ROHM Products

1. If you intend to use our Products in devices requiring extremely high reliability (such as medical equipment (Note 1), aircraft/spacecraft, nuclear power controllers, etc.) and whose malfunction or failure may cause loss of human life, bodily injury or serious damage to property ("Specific Applications"), please consult with the ROHM sales representative in advance. Unless otherwise agreed in writing by ROHM in advance, ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties arising from the use of any ROHM's Products for Specific Applications.

(Note1) Medical Equipment Classification of the Specific Applications

JAPAN	USA	EU	CHINA
CLASS III	CLASS III	CLASS II b	
CLASS IV		CLASS III	CLASS III

2. ROHM designs and manufactures its Products subject to strict quality control system. However, semiconductor products can fail or malfunction at a certain rate. Please be sure to implement, at your own responsibilities, adequate safety measures including but not limited to fail-safe design against the physical injury, damage to any property, which a failure or malfunction of our Products may cause. The following are examples of safety measures:
  - [a] Installation of protection circuits or other protective devices to improve system safety
  - [b] Installation of redundant circuits to reduce the impact of single or multiple circuit failure
3. Our Products are not designed under any special or extraordinary environments or conditions, as exemplified below. Accordingly, ROHM shall not be in any way responsible or liable for any damages, expenses or losses arising from the use of any ROHM's Products under any special or extraordinary environments or conditions. If you intend to use our Products under any special or extraordinary environments or conditions (as exemplified below), your independent verification and confirmation of product performance, reliability, etc, prior to use, must be necessary:
  - [a] Use of our Products in any types of liquid, including water, oils, chemicals, and organic solvents
  - [b] Use of our Products outdoors or in places where the Products are exposed to direct sunlight or dust
  - [c] Use of our Products in places where the Products are exposed to sea wind or corrosive gases, including Cl<sub>2</sub>, H<sub>2</sub>S, NH<sub>3</sub>, SO<sub>2</sub>, and NO<sub>2</sub>
  - [d] Use of our Products in places where the Products are exposed to static electricity or electromagnetic waves
  - [e] Use of our Products in proximity to heat-producing components, plastic cords, or other flammable items
  - [f] Sealing or coating our Products with resin or other coating materials
  - [g] Use of our Products without cleaning residue of flux (Exclude cases where no-clean type fluxes is used. However, recommend sufficiently about the residue.); or Washing our Products by using water or water-soluble cleaning agents for cleaning residue after soldering
  - [h] Use of the Products in places subject to dew condensation
4. The Products are not subject to radiation-proof design.
5. Please verify and confirm characteristics of the final or mounted products in using the Products.
6. In particular, if a transient load (a large amount of load applied in a short period of time, such as pulse, is applied, confirmation of performance characteristics after on-board mounting is strongly recommended. Avoid applying power exceeding normal rated power; exceeding the power rating under steady-state loading condition may negatively affect product performance and reliability.
7. De-rate Power Dissipation depending on ambient temperature. When used in sealed area, confirm that it is the use in the range that does not exceed the maximum junction temperature.
8. Confirm that operation temperature is within the specified range described in the product specification.
9. ROHM shall not be in any way responsible or liable for failure induced under deviant condition from what is defined in this document.

## Precaution for Mounting / Circuit board design

1. When a highly active halogenous (chlorine, bromine, etc.) flux is used, the residue of flux may negatively affect product performance and reliability.
2. In principle, the reflow soldering method must be used on a surface-mount products, the flow soldering method must be used on a through hole mount products. If the flow soldering method is preferred on a surface-mount products, please consult with the ROHM representative in advance.

For details, please refer to ROHM Mounting specification

## Precautions Regarding Application Examples and External Circuits

1. If change is made to the constant of an external circuit, please allow a sufficient margin considering variations of the characteristics of the Products and external components, including transient characteristics, as well as static characteristics.
2. You agree that application notes, reference designs, and associated data and information contained in this document are presented only as guidance for Products use. Therefore, in case you use such information, you are solely responsible for it and you must exercise your own independent verification and judgment in the use of such information contained in this document. ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties arising from the use of such information.

## Precaution for Electrostatic

This Product is electrostatic sensitive product, which may be damaged due to electrostatic discharge. Please take proper caution in your manufacturing process and storage so that voltage exceeding the Products maximum rating will not be applied to Products. Please take special care under dry condition (e.g. Grounding of human body / equipment / solder iron, isolation from charged objects, setting of Ionizer, friction prevention and temperature / humidity control).

## Precaution for Storage / Transportation

1. Product performance and soldered connections may deteriorate if the Products are stored in the places where:
  - [a] the Products are exposed to sea winds or corrosive gases, including Cl<sub>2</sub>, H<sub>2</sub>S, NH<sub>3</sub>, SO<sub>2</sub>, and NO<sub>2</sub>
  - [b] the temperature or humidity exceeds those recommended by ROHM
  - [c] the Products are exposed to direct sunshine or condensation
  - [d] the Products are exposed to high Electrostatic
2. Even under ROHM recommended storage condition, solderability of products out of recommended storage time period may be degraded. It is strongly recommended to confirm solderability before using Products of which storage time is exceeding the recommended storage time period.
3. Store / transport cartons in the correct direction, which is indicated on a carton with a symbol. Otherwise bent leads may occur due to excessive stress applied when dropping of a carton.
4. Use Products within the specified time after opening a humidity barrier bag. Baking is required before using Products of which storage time is exceeding the recommended storage time period.

## Precaution for Product Label

A two-dimensional barcode printed on ROHM Products label is for ROHM's internal use only.

## Precaution for Disposition

When disposing Products please dispose them properly using an authorized industry waste company.

## Precaution for Foreign Exchange and Foreign Trade act

Since concerned goods might be fallen under listed items of export control prescribed by Foreign exchange and Foreign trade act, please consult with ROHM in case of export.

## Precaution Regarding Intellectual Property Rights

1. All information and data including but not limited to application example contained in this document is for reference only. ROHM does not warrant that foregoing information or data will not infringe any intellectual property rights or any other rights of any third party regarding such information or data.
2. ROHM shall not have any obligations where the claims, actions or demands arising from the combination of the Products with other articles such as components, circuits, systems or external equipment (including software).
3. No license, expressly or implied, is granted hereby under any intellectual property rights or other rights of ROHM or any third parties with respect to the Products or the information contained in this document. Provided, however, that ROHM will not assert its intellectual property rights or other rights against you or your customers to the extent necessary to manufacture or sell products containing the Products, subject to the terms and conditions herein.

## Other Precaution

1. This document may not be reprinted or reproduced, in whole or in part, without prior written consent of ROHM.
2. The Products may not be disassembled, converted, modified, reproduced or otherwise changed without prior written consent of ROHM.
3. In no event shall you use in any way whatsoever the Products and the related technical information contained in the Products or this document for any military purposes, including but not limited to, the development of mass-destruction weapons.
4. The proper names of companies or products described in this document are trademarks or registered trademarks of ROHM, its affiliated companies or third parties.

**General Precaution**

1. Before you use our Products, you are requested to carefully read this document and fully understand its contents. ROHM shall not be in any way responsible or liable for failure, malfunction or accident arising from the use of any ROHM's Products against warning, caution or note contained in this document.
2. All information contained in this document is current as of the issuing date and subject to change without any prior notice. Before purchasing or using ROHM's Products, please confirm the latest information with a ROHM sales representative.
3. The information contained in this document is provided on an "as is" basis and ROHM does not warrant that all information contained in this document is accurate and/or error-free. ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties resulting from inaccuracy or errors of or concerning such information.